BHADRAVATI DIVISION.

Abstract Notification.

The attention of the public is invited to the notices published on pages noted against each of part VI of the *Mysore Gazette*, dated the June 1929, calling for tenders for the following up to 10th July 1929 :—

		Page number of the *Mysore Gazette*, *re* detailed notice.
1.	Uprooting, collecting and rough dressing dead sandal wood and ground hidden roots and of carting the same to the Sandal Kotis in all the Ranges of the Division for the year 1929-30.	.....
2.	Preparation of Sandalwood at the Tarikere Sandal Koti for 1929-30	.....
3.	Carting of prepared sandalwood from the Tarikere Sandal Koti to the Railway Station, Tarikere and loading the same to waggons for the year 1929-30	.....
4.	For unloading the timber from the Railway trucks to the depot and *vice versa* in the several Stations, during the year 1929-30	.....

H. S. RANGACHAR,
For *District Forest Officer.*

ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Dated 16th June 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 12th July 1929, for Restoring Mangasandra Vottikere Tank, Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for Restoring Mangasandra Vottikere Tank, Kolar Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate of Restoring Mangasandra Vottikere tank of Kolar Register No. 200.

No.	Details of work	Per	Quantity	Rate	Cost	Total
	Bund R. L. 55·00			Rs. a. p.	Rs.	
1	Earthwork to bund watering. and tamping, etc., complete with consolidation with lead and lift.	C.yds.	5,490			
2	Earthwork to bund in lowest portion do to be done in layers of 6″ with special watering and tamping.	,,	413			
3	Turfing	S.yds.	3,357			
4	Removing and resetting old stone with jelly.	C.yds.	52			
5	New stone work as per statement ...	,,	893			
6	Fixing grade stones with numbering and painting, etc., complete.	No.	14			
7	Index stones	,,	14			
8	B. M. Stones	,,	2			
9	Registered No. stone	,,	1			
10	Gauge Stone	,,	1			
11	Clearing jungle including cutting trees and removing roots and on hills, etc., complete.	L.S.	...			
12	Earthwork excavation for core wall in hard soil.	C.yds.	13			
13	Concrete for foundation of core wall ..	C.ft.	90			
14	Burnt brick in surki for core wall ...	,,	448			
15	Plastering the same	Sqr.	5·52			
16	Puddle wall with good clay ...	C.yds.	88			
	Total to bund ..	...	...	...	...	...
	Sluice R. L. 45·00.					
17	Earthwork excavation	C.yds.	18			
18	Refilling same with watering and tamping.	,,	18			
19	Concrete for foundation	C.ft.	277			
20	Burnt brick in surki mortar ...	C.ft.	167			
21	Burnt stone slabs 4″ to 6″ thick ...	S.ft.	170			
22	Plastering with surki mortar ...	Sqr.	2·75			
23	Plug and rod with locking arrangement as per standard design.	L.S.	...			
24	Boring holes, etc., in cross and orifice slabs.	L.S.	...			
	Total sluice ...	...	...	..	...	...
	Weir R. L. 50·00.					
25	Earthwork excavation for body wall ...	C.yds.	39			
26	Concrete for foundation	C.ft.	112			
27	Burnt brick in surki mortar ...	,,	540			
28	Burnt stone slabs 4″ to 6″ thick ...	S.ft.	76			
29	Plastering with surki mortar ...	Sqr.	6·76			
30	Rough stone for apron	C.yds.	64			
	Total weir ...	...	...	...	...	...
	Total of bund, sluice and weir contingencies.	...	...	...	...	...
	Grand Total Rs. ...	...	...	...	...	...

Notice dated 16th June 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 12th July 1929 for restoring Hirenagavalli Jonalkunte Tank, Chickballapur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M., and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 only in cash or Government Promissory Notes, as earnest money and be superscribed " Tender for Restoring Hirenagavalli Jonalkunte Tank, Chikballapur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Detailed abstract Estimate of Restoring Jonakunte Reg. No. 104 (Hirenagvally Jonalkunte) of Chikballapur Taluk.

No.	Particulars of work	Per	Quantity	Rate	Cost	Total
	Bund.			Rs. a. p.	Rs.	
1	Earth work watering and tamping, etc., complete including lead and lift.	C.yd.	6,663			
2	Turfing	S.yd.	5,992			
3	New stone revetment	C.yd.	353			
4	Resetting old stone revetment wherever necessary.	Lump	sum			
5	Grade stones carving figurs painting and fixing, etc., complete.	Each	19			
6	Index stones do do ...	,,	19			
7	Register No. stones do ...	,,	1			
8	B. M. stones do ...	,,	2			
9	Gauge stone do ...	,,	1			
10	Removing ant hills here and there and cutting trenches to old bund Grade.	,,	14			
	Total Bund ...	...	...	...	..	...
1	Earth work excavation	C.yd.	65			
2	Refilling the earth with watering and consolidation.	,,	65			
3	Surki mortar concrete	C.ft.	489			
4	Burnt brick in surki mortar ...	,,	328			
5	Burnt stone slabes 6" to 4" thick ...	S.ft	252			
6	Plastering with surki mortar ...	Sqr.	6·68			
7	Drilling holes in cross orifice Gebbet slabs.	No.	6			
8	Providing plug and rod with locking arrangement.	Lump	sum			
9	Cut open the bund at old sluice site and removing sluice and refilling the earth with watering and consolidation, etc., and dismantling masonry work and blocking up the old sluice.	,,	,,			

No.	Particulars of work	Per	Quantity	Rate	Cost	Total
	Weir.			Rs. a. p.	Rs.	
1	Earth work excavation	C.yd.	.42			
2	Concrite in surki mortar	C.ft.	169			
3	Burnt brick in surki mortar ...	,,	861			
4	Burnt stone slabs 4″ to 6″ thick ...	Sqr.	361			
5	Plastering with surki mortar ...	,,	11·09			
6	New stone work	C.yd.	119			
7	Providing joggle joints	No.	12			
8	New stone pitching to sides of cart track	C.yd.	40			
	Total to weir ...	...	...	...	...	...
	Contingencies ...	...	...	...	..	...
	Grand total ...	...	...	...	...	...

Abstract Notification dated 12th June 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 602 and 603, dated 20th June 1929, calling for tenders for Restoring Kiruvani Major Tank, Mulbagal Taluk.

The last date of tender is 5th July 1929.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE DIVISION.

Notice No. 1680—2, *dated 7th June* 1929,

RESTORING KULUGERE DODDAKERE MAJOR TANK, MALVALLI TALUK.

"Reference is invited to the advertisement published in detail in the *Mysore Gazette*, dated 13th June 1929 intimating the last date of tender for restoring Kulugere Doddakere Major Tank, Malvalli Taluk."

N. KRISHNIENGAR,
Executive Engineer.

SHIMOGA ARASALU RAILWAY, CONSTRCTION DIVISION.

Abstract Notification dated 14th June 1929.

The attention of the public is invited to the Notification dated 8th June 1929, calling for tenders for construction of buildings on Shimoga-Arasalu Railway, published in extenso in page 590 part VI of *Mysore Gazette*, dated 13th June 1929. The last date for receiving tenders is 3rd July 1929 up to 12 noon.

Tender forms can be had from the undersigned on payment of Re. 1 per form.

Y. K. RAMACHANDRA RAO,
Executive Engineer

KADUR DIVISION.

Abstract Notification dated 6th June 1929.

"The attention of the public is invited to the notice calling for tenders for constructing "*A New Dispensary*" at Javali Mudigere Taluk, latest date for receiving tenders 1st July 1929, deposit Rs. 500".

B. KRISHNA RAO,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is hereby invited to the advertisement Page 604, published on the Part VI of the *Mysore Gazette*, dated 20th June 1929, calling tenders for the work of restoring Sringere Hanumanhalli, Minor tank, Register No. 171 of Holalkere Taluk.

Abstract Notification.

The attention of the public is hereby invited to the advertisement page 605 and 606, published in Part VI of the *Mysore Gazette*, dated 20th June 1929, calling for tenders for the work of closing the Breach of Bethur Tank, Register No. 15 of Davangere Taluk.